e-mail:eenorth2@bwssb.gov.in

TELE PHONE – (080) – 29565615

BANGALORE WATER SUPPLY AND SEWERAGE BOARD

Office of the Executive Engineer, North-2 Division Pinakini Bhavan, Doddaballapur Main Road, Yelahanka New Town, Bangalore-64.

No. BWSSB/ENTE/AE-1/ 1572 /2025-26 Date: 01.08.2025

Corrigendum

Sub: Providing and laying 230mm dia GSW line at Chitra layout coming under Yelahanka New Town S/stn of AEEN-2-1 sub division.

Ref: **IFTNo : BWSSB/2025-26/WS/WORK_INDENT2359**

****

With reference to the above subject, in the Schedule B of above reference tender the following corrigendum is issued for further action.

Sl No	Existing	To be read as
Code08	Providing and laying Bituminous Macadam with 100 tph capacity hot mix plant batch type using crushed aggregates of specified grading premixed with bituminous binderVG-30 @ 3.3% by weight of mix, transported to site, laid over a previously prepared surface with mechanical paver finisher to the required grade, level and alignment and rolled as per clauses501.6 and 501.7 to achieve the desired compaction	Providing and laying Dense Graded Bituminous Macadam with120 TPH capacity HMP batch type using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.
Code09	Providing and laying Dense Graded Bituminous Macadam with120 TPH capacity HMP batch type using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with	Removal of Unserviceable Soil with Disposal up to a suitable distance as directed by the Engineer in charge of work

Scanned with OKEN Scanner

	mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.	

Executive Engineer
North-2 Division, BWSSB
Pinakini Bhavan, Doddaballapur Main road,
Yelahanka New Town, Bangalore-64.

Scanned with OKEN Scanner